Public Works (1907) Department.

G.O., No. 462 / 463 } 9

DATED 16-10-1907.

23. 10. 07

10 copies of G.O.
2 copies of G.O. with docket at the back for the Govt of India.

[Despatch Abstract.]

Lascars' sheds at Peranai & a culvert across Vilangal channel, Madura Dt.

An estimate, amounting to Rs 3075, for constructing —— sanctioned, and a copy of the Pro: ordered to be forwarded to the Govt. of India for information

Lascars' sheds at Peranai & a culvert across Vilangal channel, Madura Dt.

Forwarding the Govt. of India an estimate amounting to Rs 3075, for constructing ——

[P. W. 26. 2,000—6-7-06.]

Indexed.

ASM 16/X

Issued 21/10/07.

112 J. of 07.08 Registered 18-10-07

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

IRRIGATION.
ACCOUNT.

Government of Madras.

PUBLIC WORKS DEPARTMENT.

Recd. } 1907. *Enclosures*

Regd. *Spare copies*

G.O., No. 462 I., 16th October 1907.

Lascars' sheds at Peranai and a culvert across Vilangal channel, Madura district

An estimate, amounting to Rs. 3,075, for constructing —, sanctioned, and a copy of the Proceedings ordered to be forwarded to the Government of India for information.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Irrigation.
Account.

READ—the following papers :—

I

Letter—from C. W. WOOD, Esq., Superintending Engineer, VI Circle.
To—the Chief Engineer for Irrigation.
Dated—Trichinopoly, the 6th September 1907.
No.—485 C.E.

I have the honour to forward herewith, for your approval and sanction of Government, an estimate, amounting to Rs. 2,450, for constructing sheds for the lascars employed at the head works at Peranai (Periyár project) in the Madura district.

2. As the old Peranai anicut has been completely demolished and the new regulator works fully completed, the number of lascars employed for regulating the shutters (of the regulator scouring sluices and the head sluice) at the head works has been increased from 6 to 10. As it is essential that these men should live near the head works so that their services may be readily available on emergencies, it is proposed to build quarters for them.

3. At present, as explained in the report attached to the estimate, quarters are available only for two men. Provision has therefore been made in the estimate for constructing eight more huts. These huts will be built according to the standard design for quarters for constables, issued with G.O., No. 1778 W., dated 24th August 1906. The site plan attached shows the position of these buildings. At the crossing of the Vilangal channel, a culvert will be constructed according to the plan enclosed. As the site required for these huts has, it is understood, been obtained in exchange for Government waste lands, no provision has been made in the estimate for land compensation.

4. In the report attached to the estimate, the Executive Engineer fully explains the necessity for and the details of the works proposed.

5. As these huts are required in the interests of the Periyár project, the proposed outlay should be charged to the open capital account of the project.

6. The rates are fair and I request you to be so good as to obtain early sanction of Government to the estimate in question.

ENCLOSURE.

Report to accompany the estimate for constructing lascars, shed and a culvert across the Vilangal channel at Peranai.

	RS.
Amount of estimate	2,500

The estimate has been called for by the Superintending Engineer in his No. 4714, dated 28th November 1906.

There are at present six lascars at Peranai. It is not possible to regulate the head works with less than ten men. Mr. S. D. Pears during his inspection of Peranai ordered an estimate to be sent up for building quarters for the required accommodation and approved of the site which has since been exchanged for some poramboke land of the old Vadagarai channel which was not wanted by the Public Works Department.

There are at present two blocks of buildings available in the compound for housing the whole of the staff. The eastern block will be set apart for the sub-overseer, telephone shed, and store rooms. The western block will house the head lascar, one lascar the kitchen. The fourth room in it being used as a godown for servants and peons. New quarters are wanted for eight lascars. They will be built as settled by Mr. Pears in two blocks at the site shown. The design will be similar to the revised type design for police huts approved in G.O., No. 1778 W., dated 24th August 1906 (copy of the design enclosed).

A culvert to cross the Vilangal channel is necessary and will be built as shown on the plan.

A. R. deChazal,
Executive Engineer, Madura Division

10th July 1907.

II

Note by the Chief Engineer for Irrigation.

The amount of the estimate has been increased in this office from Rs. 2,450 to Rs. 2,500 owing to the addition of wings in front and rear to the proposed culvert across Vilangal channel to suit earth slopes of 1 to 1. The estimate, as altered, is recommended for sanction.

H. E. Clerk,
Ag. Chief Engineer for Irrigation.

10th October 1907.

Order—No. 462 I., dated 16th October 1907.

The following estimate is sanctioned :—

Imperial.

Capital expenditure not charged to Revenue.

49. Irrigation.

Periyár Project.

Open Capital Account.

I. Works.

1. Head Works.

K. Buildings.

Unremunerative work.

Constructing lascars' sheds at Peranai and a culvert across Vilangal channel.

Estimate—

	RS.
I. Works	2,500
II. Establishment	575
Total ...	3,075

2. This sanction is registered as No. 112 I. of 1907-1908 and will expire on 31st March 1909.

3. Ordered that a copy of these Proceedings be forwarded to the Government of India for information.

[Here enter No. 463 I., dated 16th October 1907.]

(True Extract.)

H. E. CLERK,
Ag. Joint Secy. to Govt., P.W.D.,
Irrigation Branch.

To the Chief Engineer for Irrigation.
" Superintending Engineer, VI Circle (with estimate).
" Examiner, Public Works Accounts.

Forwarded to the

(By order.)

Registrar.

No. 462 I., 16TH OCTOBER 1907.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Irrigation.
Account.

READ—the following papers:—

I

Letter—from C. W. WOOD, Esq., Superintending Engineer, VI Circle.
To—the Chief Engineer for Irrigation.
Dated—Trichinopoly, the 6th September 1907.
No.—485 C.E.

I have the honour to forward herewith, for your approval and sanction of Government, an estimate, amounting to Rs. 2,450, for constructing sheds for the lascars employed at the head works at Peranai (Periyár project) in the Madura district.

2. As the old Peranai anicut has been completely demolished and the new regulator works fully completed, the number of lascars employed for regulating the shutters (of the regulator scouring sluices and the head sluice) at the head works has been increased from 6 to 10. As it is essential that these men should live near the head works so that their services may be readily available on emergencies, it is proposed to build quarters for them.

3. At present, as explained in the report attached to the estimate, quarters are available only for two men. Provision has therefore been made in the estimate for constructing eight more huts. These huts will be built according to the standard design for quarters for constables, issued with G.O., No. 1778 W., dated 24th August 1906. The site plan attached shows the position of these buildings. At the crossing of the Vilangal channel, a culvert will be constructed according to the plan enclosed. As the site required for these huts has, it is understood, been obtained in exchange for Government waste lands, no provision has been made in the estimate for land compensation.

4. In the report attached to the estimate, the Executive Engineer fully explains the necessity for and the details of the works proposed.

5. As these huts are required in the interests of the Periyár project, the proposed outlay should be charged to the open capital account of the project.

6. The rates are fair and I request you to be so good as to obtain early sanction of Government to the estimate in question.

ENCLOSURE.

Report to accompany the estimate for constructing lascars, shed and a culvert across the Vilangal channel at Peranai.

	RS.
Amount of estimate	2,500

The estimate has been called for by the Superintending Engineer in his No. 4714, dated 28th November 1906.

There are at present six lascars at Peranai. It is not possible to regulate the head works with less than ten men. Mr. S. D. Pears during his inspection of Peranai ordered an estimate to be sent up for building quarters for the required accommodation and approved of the site which has since been exchanged for some poramboke land of the old Vadagarai channel which was not wanted by the Public Works Department.

There are at present two blocks of buildings available in the compound for housing the whole of the staff. The eastern block will be set apart for the sub-overseer, telephone shed, and store rooms. The western block will house the head lascar, one lascar the kitchen. The fourth room in it being used as a godown for servants and peons. New quarters are wanted for eight lascars. They will be built as settled by Mr. Pears in two blocks at the site shown. The design will be similar to the revised type design for police huts approved in G.O., No. 1778 W., dated 24th August 1906 (copy of the design enclosed).

A culvert to cross the Vilangal channel is necessary and will be built as shown on the plan.

A. R. DECHAZAL,
Executive Engineer, Madura Division

10th July 1907.

II

Note by the Chief Engineer for Irrigation.

The amount of the estimate has been increased in this office from Rs. 2,450 to Rs. 2,500 owing to the addition of wings in front and rear to the proposed culvert across Vilangal channel to suit earth slopes of 1 to 1. The estimate, as altered, is recommended for sanction.

H. E. CLERK,
Ag. Chief Engineer for Irrigation.

10th October 1907.

Order—No. 462 I., dated 16th October 1907.

The following estimate is sanctioned :—

Imperial.

Capital expenditure not charged to Revenue.

49. Irrigation.

Periyár Project.

Open Capital Account.

I. Works.

1. Head Works.

K. Buildings.

Unremunerative work.

Constructing lascars' sheds at Peranai and a culvert across Vilangal channel.

Estimate—

	RS.
I. Works	2,500
II. Establishment	575
Total ...	3,075

2. This sanction is registered as No. 112 I. of 1907–1908 and will expire on 31st March 1909.

3. Ordered that a copy of these Proceedings be forwarded to the Government of India for information.

[Here enter No. 463 I., dated 16th October 1907.]

(True Extract.)

H. E. CLERK,
Ag. Joint Secy. to Govt., P.W.D.,
Irrigation Branch.

To the Chief Engineer for Irrigation.
" Superintending Engineer, VI Circle (with estimate).
" Examiner, Public Works Accounts.

Endorsement—No. 463 I., dated 16th October 1907.

Forwarded.

(By order.)

H. E. CLERK,
Ag. Joint Secy. to Govt., P.W.D.,
Irrigation Branch.

IRRIGATION.
ACCOUNT.

Government of Madras.

PUBLIC WORKS DEPARTMENT.

Recd.	1907.	*Enclosures*
Regd.		*Spare copies*

G.O., Nos. 462, 463 I., 16th October 1907.

Lascars' sheds at Peranai and a culvert across Vilangal channel, Madura district

Forwarding to the Government of India an estimate, amounting to Rs. 3,075, for constructing

—.

1,000—20-9-06.

NOTES.

Estimate amounting to Rs.2450, for constructing 8 sheds for lascars employed at the Peranai, Periyar headworks Project.

+ a culvert across Vilangal channel

P.W.D., Irrigation.

(C.No.5814) From the Superintending Engineer VI Circle, No.485 C.E. dated 6th September 1907.

D.I.

Orders are requested whether the estimate may be checked for sanction.

19.9.07.

19/9/07

21/9/07

21/9/07

CET
SB
23.9.07

The estimate has been checked; wings ~~[illegible]~~ in front & rear to the proposed culvert across Vilangal chal have been added to suit earth slopes of 1½:1. The estimate has been increased from Rs 2450 to Rs 2,500.

4.10.07. 8.10.07.

A draft order sanctioning the estimate is submitted, and if approved, may be circulated to H.E.

8.10.07

10/10/07

✓

Submitted to H E the Governor

D.I. for perusal

[illegible] 11/10

Estimate amounting to Rs 2500 (exclusive of establishment charges) for constructing 8 huts for lascars at Peranai and a culvert across the Vilangal Channel

The old anicut at Peranai (Madura District) has recently been replaced by a regulator, and an increased staff of 10 men are required to work and look after the shutters. There are now only quarters for 2 men and 8 more are required. The culvert is to provide access to the huts.

A draft ~~estimate~~ order sanctioning the estimate is submitted

[illegible] 10/10/07

Appd. [illegible] 12.10.07

DI

Submitted that the draft order may now issue

[illegible] 12.10.07

[C. No. 5814] Subject- Estimate for constructing 8 sheds for lascars employed at the Peranai head works Periyar Project & a culvert across Vilangal channel.

PUBLIC WORKS DEPARTMENT CURRENT No. 7592
IRRIGATION BRANCH. PASSED ON BY
R. C. 16/10/07
PROCEEDINGS OF THE MADRAS GOVERNMENT.
REF.
R. K.
D. O.

Print with Report

READ the following

P. 1-7 Letter from the S.E. VI Circle No. 485 C.E. dy 6-9-1907

3-6

Note by the Chief Engineer for Irrigation

The amount of the Estimate has been increased in this office from Rs 2450 to Rs 2500 owing to the addition of wings in front and rear to the proposed culvert across Vilangal channel to suit earth slopes of 1 to 1. The Estimate as altered is recommended for sanction

---

Issue

D.I. 14/10.

Irrig. Reed

12.10.07

Order No. 462 I dy 16-10-1907
The following Estimate is sanctioned:

Imperial

Capital Expenditure not charged to Revenue

49. Irrigation

Periyar Project

Open Capital Account

2

4/

I works

1. Head works.

K. Buildings

Unremunerative work.

Constructing lascars sheds at Perani and a culvert across Vilangal channel.

Estimate.

I works	Rs 2500
II Establishment	Rs 575
Total	Rs 3075

2. This sanction is registered as No 112 I of 1907-08 and will expire on 31. 3. 1909

3. Ordered that a copy of these Proceedings be forwarded to the Govt of India for information.

[H. E. No. 463 I. dt 16-10-1907]

Forwarded

DESPATCHED
13 NOV 1907

20

The Chief Engr for Irrgn

Supg Engr VI Circle w/ Estt:

Examr, PW Accts

Mh
8. 10. 07

Ordinary Press

E. I. Form No. 1 (c)—1,000—10-3-05.